

## **1 GENERAL**

### **1.1 SUMMARY OF WORK**

- .1 This Section specifies stone fibre board insulation for curtain wall, and, other board insulation applications.

### **1.2 RELATED REQUIREMENTS**

- .1 Section [07 44 00 - Curtain Walls and Glazed Assemblies].
- .2 Section [07 92 19 - Acoustical Joint Sealants].

### **1.3 REFERENCE STANDARDS**

- .1 ASTM International (ASTM).
  - .1 ASTM C165 - [2012], Standard Test Method for Measuring Compressive Properties of Thermal Insulations.
  - .2 ASTM C356 - [2010], Standard Test Method for Linear Shrinkage of Preformed High-Temperature Thermal Insulation Subjected to Soaking Heat.
  - .3 ASTM C411 - [2011], Standard Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation.
  - .4 ASTM C518 - [2010], Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus.
  - .5 ASTM C612 - [2010], Standard Specification for Mineral Fiber Block and Board Thermal Insulation.
  - .6 ASTM C665 - [2011], Standard Specification for Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing.
  - .7 ASTM C795 - [2013], Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel.
  - .8 ASTM C1104/C1104M - [2013], Standard Test Method for Determining the Water Vapor Sorption of Unfaced Mineral Fiber Insulation.
- .2 Canada Green Building Council (CaGBC).
  - .1 LEED v4-[2014], LEED (Leadership in Energy and Environmental Design): Green Building Rating System.
- .4 Underwriters' Laboratories of Canada (ULC).
  - .1 CAN/ULC S102-[2010], Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
  - .2 CAN/ULC S114-[2005], Standard Method of Test for Determination of Non-Combustibility in Building Materials.

### **1.4 ADMINISTRATIVE REQUIREMENTS**

- .1 Co-ordination: Co-ordinate work of this Section with roofing or deck work and with work of other trades for proper time and sequence to avoid construction delays.
- .2 Pre-installation Meeting: Convene pre-installation meeting after Award of Contract and [one week] before starting work of this Section to verify project requirements, substrate conditions and coordination with other building sub-trades, and to review manufacturer's written installation instructions.
  - .1 Comply with Section 01 31 19 - Project Meetings and co-ordinate with other similar pre-installation meetings.
  - .2 Notify attendees 2 weeks prior to meeting and ensure meeting attendees include as minimum:
    - .1 Owner;
    - .2 Consultant;
    - .3 Board Insulation Installation Subcontractor;
    - .4 Manufacturer's Technical Representative.

- .3 Ensure meeting agenda includes review of methods and procedures related to insulation installation including co-ordination with related work.
- .4 Record meeting proceedings including corrective measures and other actions required to ensure successful completion of work and distribute to each attendee within 1 week of meeting.

## 1.5 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Make submittals in accordance with Contract Conditions and Section 01 33 00 - Submittal Procedures.
- .2 Product Data: Submit product data including manufacturer's literature for insulation materials and accessories, indicating compliance with specified requirements and material characteristics.
  - .1 Submit list on insulation manufacturer's letterhead of materials and accessories to be incorporated into Work.
  - .2 MSDS report.
  - .3 Include product name.
  - .4 Include preparation instructions and recommendations, installation methods, and storage and handling requirements.
  - .5 Include contact information for manufacturer and their representative for this Project.
- .3 Samples:
  - .1 Submit [140 x 190] mm minimum sample of insulation in thickness used on Project.
- .4 Test Reports:
  - .1 Submit evaluation service reports or other independent testing agency reports showing compliance with specified performance characteristics and physical properties.
- .5 Field Reports: Submit manufacturer's field reports within 3 days of each manufacturer representative's site visit and inspection.
- .6 Sustainable Design (LEED).
  - .1 LEED Submittals: In accordance with Section [01 35 21 – LEED Requirements]
  - .2 Submit verification for items as follow:
    - .1 EA Credit 1: Thermal value of insulation contributing to overall energy performance of building.
    - .2 MR Credits 4: Recycled content of insulation indicating percentages by weight of preconsumer and postconsumer recycled content.
    - .3 MR Credits 5: Verify location where insulation is extracted, processed and manufactured.
- .7 Insulation Installer Qualifications:
  - .1 Submit letter verifying insulation installer's experience with work similar to work of this Section.

## 1.6 CLOSEOUT SUBMITTALS

- .1 Operation and Maintenance Data: Supply maintenance data for insulation materials for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.
- .2 Sustainable Design Closeout Documentation (LEED).
  - .1 Provide calculations on end-of-project recycling rates, salvage rates, and landfill rates for work of this Section demonstrating percentage of construction wastes which were recycled.
  - .2 Submit verification from recycling facility showing receipt of materials.
- .3 Record Documentation: In accordance with Section 01 78 00 - Closeout Submittals.
  - .1 List materials used in insulation work.
  - .2 Warranty: Submit warranty documents specified.

## 1.7 QUALITY ASSURANCE

- .1 Board Insulation Installer Quality Assurance: Work experience of [5] years minimum with work similar to work of this Section.

- .2 Sustainability Standards Certification (LEED).
  - .1 LEED Canada submittals: In accordance with Section 01 35 21 - LEED Requirements.

## 1.8 DELIVERY STORAGE AND HANDLING

- .1 Delivery and Acceptance Requirements:
  - .1 Deliver material in accordance with Section 01 61 00 - Common Product Requirements.
  - .2 Deliver materials and accessories in insulation manufacturer's original packaging with identification labels intact and in sizes to suit project.
  - .3 Ensure insulation materials are not exposed to moisture during delivery.
  - .4 Replace wet or damaged insulation materials.
- .2 Storage and Handling Requirements: Store materials off ground in dry location and protected from exposure to harmful weather conditions and at temperature conditions recommended by manufacturer.
  - .1 Store in original packaging until installed.
- .3 Packaging Waste Management:
  - .1 Separate and recycle waste packaging materials in accordance with Section 01 74 19 - Construction Waste Management and Disposal.
  - .2 Remove waste packaging materials from site and dispose of packaging materials at appropriate recycling facilities.
  - .3 Collect and separate for disposal paper and plastic material in appropriate on-site storage containers for recycling [in accordance with Waste Management Plan].

## 1.9 WARRANTY

- .1 Project Warranty: Refer to Contract Conditions for project warranty provisions.
- .2 Manufacturer's warranty: Submit, for Owner's acceptance, manufacturer's standard warranty document executed by authorized company official. Manufacturer's warranty is in addition to and not intended to limit other rights Owner may have under Contract Conditions.
- .3 Warranty period: [1] years commencing on Date of Substantial Performance of Work.

## 2 PRODUCTS

### 2.1 MANUFACTURER

- 1. Manufacturer: ROCKWOOL, 8024 Esquesing Line, Milton, Ontario, L9T 6W3, Phone: 905-878-8474, Toll Free:-800-265-6878, e-mail: [contactus@rockwool.com](mailto:contactus@rockwool.com), URL: [www.rockwool.com](http://www.rockwool.com)

### 2.2 DESCRIPTION

- .1 Non-combustible, semi-rigid, water repellent, mineral wool insulation board for exterior curtain wall systems to ASTM C612, Type IVB.

### 2.3 PERFORMANCE CRITERIA

- .1 Board insulation for exterior curtain wall systems: To ASTM C612, Type IVB.
  - .1 Fire performance:
    - .1 Non-combustibility: To CAN/ULC S114.
    - .2 Surface Burning Characteristics: To CAN/ULC S102.
      - .1 Flame spread: 0.
      - .2 Smoke developed: 0.
  - .2 Thermal resistance (RSI value/25.4 mm at 24 ° C: [0.75] m<sup>2</sup>K/W to ASTM C518.
  - .3 Moisture sorption: [0.01] % to ASTM C1104/C1104M.
  - .4 Dimensional stability: 2 % maximum linear shrinkage at 650 °C to ASTM C356.
  - .5 Corrosive resistance:

- .1 Steel to ASTM C665: Pass.
- .2 Stainless steel to ASTM C795: Pass.
- .6 Service temperature hot surface performance: 650 °C maximum to ASTM C411.
- .7 Density: 64 kg/m<sup>3</sup> nominal to ASTM C612.
- .8 Recycled content: [40] [16] % minimum.
- .9 Acoustical performance sound absorption co-efficients to ASTM C423.

Sound Absorption Co-efficients at Frequencies

| Thickness (mm) | 125 Hz | 250 Hz | 500 Hz | 1000 Hz | 2000 Hz | 4000 Hz | NRC  |
|----------------|--------|--------|--------|---------|---------|---------|------|
| 50             | 0.26   | 0.71   | 1.14   | 1.09    | 1.04    | 1.03    | 1.00 |
| 76             | 0.65   | 0.94   | 1.13   | 1.07    | 1.06    | 1.04    | 1.05 |
| 100            | 0.92   | 1.04   | 1.07   | 1.07    | 1.07    | 1.08    | 1.05 |

## 2.4 MATERIALS

- .1 Non-combustible, semi-rigid, water repellent, mineral wool insulation board to ASTM C612, Type-IVB.
  - .1 Size: [610 x 1219] [1219 x 1828] mm.
  - .2 Thickness: [50] [76] [102] mm.
  - .3 Acceptable Material: ROCKWOOL, CURTAINROCK® 40 [with RFF Facer].

## 2.5 ACCESSORIES

- .1 Mechanical fasteners in accordance with insulation manufacturer's written recommendations.
- .2 Insulation Clips: in accordance with curtain wall manufacturer's written recommendations [and Section [07 44 00 - Curtain Walls and Glazed Assemblies].
- .4 Facings: Use only facings in accordance with insulation manufacturer's written recommendations as follows:
  - .1 RFF facer: Aluminum foil with fiberglass reinforcement to ASTM.
    - .1 Acceptable material: ROCKWOOL, RFF FACER.

## 2.6 SOURCE QUALITY CONTROL

- .1 Ensure insulation components and accessories are supplied or approved in writing by single manufacturer.

## 2.7 PRODUCT SUBSTITUTIONS

- .1 Substitutions: [In accordance with Section 01 23 13 - Product Substitution Procedures] [No substitutions permitted].

## 3 EXECUTION

### 3.1 INSTALLERS

- .1 Use only installers with [5] years minimum experience with work similar to work of this Section.

### 3.2 EXAMINATION

- .1 Verification of Conditions: Verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for insulation installation in accordance with manufacturer's written recommendations.
  - .1 Visually inspect substrate in presence of Consultant.
  - .2 Ensure surfaces are free of snow, ice, frost, grease and other deleterious materials.
  - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Consultant.

- .2 Start of insulation installation indicates installer's acceptance of substrate installation conditions.

### 3.4 INSTALLATION

- .1 General:
  - .1 Install insulation in accordance with manufacturer's written recommendations.
  - .2 Install insulation to maintain continuity of thermal protection to building elements and spaces.
  - .3 Fit insulation closely around electrical boxes, pipes, ducts, frames and other objects in or passing through insulation.
  - .4 Keep insulation minimum [75] mm from heat emitting devices such as recessed light fixtures, and minimum [50] mm from sidewalls of chimneys and vents.
  - .5 Do not enclose insulation until before inspection and receipt of Consultant's written approval.
- .2 Installation of Insulation Board for Curtain Wall Applications:
  - .1 Install insulation board in accordance with insulation manufacturer's and curtain wall manufacturer's written recommendations.
  - .2 Attach insulation using insulation clips in accordance with curtain wall manufacturer's written recommendations.
  - .3 Seal joints with acoustical joint sealant in accordance with Section [07 92 19 - Acoustical Joint Sealants].

### 3.5 FIELD QUALITY CONTROL

- .1 Field Inspection: Coordinate field inspection in accordance with Section [01 45 00 - Quality Control].
- .2 Manufacturer's Services:
  - .1 Coordinate manufacturer's services with Section [01 45 00 - Quality Control].
    - .1 Arrange for payment for manufacturer's services.
    - .2 Have manufacturer review work involved in handling, installation, protection, and cleaning of insulation and accessories, and submit written reports in acceptable format to verify compliance of Work with Contract conditions.
  - .2 Manufacturer's Field Services: Provide manufacturer's field services consisting of product use recommendations and periodic site visits for product installation review in accordance with manufacturer's instructions.
    - .1 Report any inconsistencies from manufacturer's recommendations immediately to Consultant.
  - .3 Schedule site visits to review work at stages listed:
    - .1 After delivery and storage of drainage sheet and accessories, and when preparatory work on which Work of this Section depends is complete, but before installation begins.
    - .2 Twice during progress of work at 25% and 60% complete.
    - .3 Upon completion of Work, after cleaning is carried out.
    - .4 Obtain reports within three days of review and submit immediately to Consultant.

### 3.6 CLEANING

- .1 Progress Cleaning: Perform cleanup as work progresses [in accordance with Section 01 74 00 - Cleaning and Waste Management].
  - .1 Leave work area clean at end of each day.
- .2 Final Cleaning: Upon completion, remove surplus materials, rubbish, tools, and equipment [in accordance with Section 01 74 00 - Cleaning and Waste Management].
- .3 Waste Management:
  - .1 Co-ordinate recycling of waste materials with 01 74 19 - Construction Waste Management and Disposal.
  - .2 Collect recyclable waste and dispose of or recycle field generated construction waste created during construction or final cleaning related to work of this Section.
  - .3 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

**3.7 PROTECTION**

- .1 Protect installed products and accessories from damage during construction.
- .2 Repair damage to adjacent materials caused by insulation installation.

**END OF SECTION 07 21 13 – BOARD INSULATION (CURTAINROCK® 40)**